



ADDENDUM NO. 1

May 21, 2020

**Walton County Sheriff's Office
Driver Training Pad
DeFuniak Springs, Florida
Sam Marshall Architects**

THIS ADDENDUM IS ISSUED FOR THE PURPOSE OF MODIFYING AND/OR CLARIFYING THE ORIGINAL PLANS AND SPECIFICATIONS AND IS TO BE CONSTRUED AS BEING THEREIN.

General Notes:

No change in bid date. Sealed bids will be due to the Walton County Sheriff's Office as stated but will NOT be publicly opened. Sealed bid will be opened in a closed meeting on June 1, 2020 and the results shared via email.

The owner will pay all tap / impact fees.

Project Clarifications:

Civil

1. The municipal water meter will be purchased by the owner and installed by the contractor.
2. All stormwater pipe shall be RCP.
3. Limerock shall be used for the gravel road.

Electrical

1. The AIC rating for panel MP is 14,000 AIC.
2. The rating for the enclosures is NEMA 3R lockable enclosure.
3. The electrical specifications are the notes on the drawings.
4. The ratings on the inground boxes at the base of the poles are light traffic duty, concrete, Quazztie open bottom 12" gravel under-layment.
5. The lighting controller is Manual, contractor built, in a NEMA 3R lockable enclosure with 0-10 MV dimmers.

END OF ADDENDUM